



**OIL PALM INDIA LIMITED**  
**REGISTERED OFFICE XIV/130, KOTTAYAM SOUTH P.O. 686 013**  
**Phone: 2566882, 2567103, 2567104. Fax: 0481-2561442**  
**E-mail: tendersopil@gmail.com**  
**Web: www.oilpalmindia.com**

OP/CE/262

29.04.2024

**Quotation Notice**

Competitive quotations are invited from the contractors for construction of platform for storage tank in Medicinal Plant at Kulathupuzha Nursery. Quotation should reach to the Registered Office, Oil Palm India Limited, Kottayam or above mail id on or before 2.00pm on 07.05.2024 and will be opened at 3.00pm on the same day. Rate should be quoted in the prescribed format. The work should be completed within 10 days on receipt of our work order.

  
Senior Manager (CE)



## OIL PALM INDIA LIMITED

### SCHEDULE

Name of work: Construction of platform for storage tank in Medicinal plant at Kulathupuzha estate.

Sl No.	Description	Qty	Unit	Rate in figures (excluding GST)	Rate in words	Amount (excluding GST)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil.	1.00	M <sup>3</sup>			
2	Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15 cm or nearest available size conforming to IS 2185 part I of 1979 for foundation and plinth with thickness 15cm in CM 1:6 (1 Cement : 6 Coarse sand) etc. complete.	1.00	M <sup>3</sup>			
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers consolidating each deposited layer by ramming and watering, lead up to 50m.	2.10	M <sup>3</sup>			
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	1.50	M <sup>3</sup>			
5	Plastering with cement mortar 1:4, 12mm thick	20	M <sup>2</sup>			
	<b>TOTAL</b>					

I .....here by agree to undertake to execute the work at the rate noted against each item.

Contractor

  
Senior Manager (Est)